

FORM
5

Rev
10/14

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402048876

Date Received:

05/30/2019

DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type Final completion Preliminary completion

OGCC Operator Number: 18600 Contact Name: Anthony Trinko
Name of Operator: COLORADO INTERSTATE GAS COMPANY LLC Phone: (719) 520-4557
Address: P O BOX 1087 Fax:
City: COLORADO SPRINGS State: CO Zip: 80944 Email: anthony_trinko@kindermorgan.com

API Number 05-009-05083-00 County: BACA
Well Name: FLANK Well Number: 27
Location: QtrQtr: NWSE Section: 33 Township: 33S Range: 42W Meridian: 6
FNL/FSL FEL/FWL
Footage at surface: Distance: 1980 feet Direction: FSL Distance: 1980 feet Direction: FEL
As Drilled Latitude: 37.125584 As Drilled Longitude: -102.156330
GPS Data:
Date of Measurement: 09/22/2009 PDOP Reading: 2.5 GPS Instrument Operator's Name: G.H. Jarrell
FNL/FSL FEL/FWL
** If directional footage at Top of Prod. Zone Dist: feet Direction: Dist: feet Direction:
Sec: Twp: Rng:
FNL/FSL FEL/FWL
** If directional footage at Bottom Hole Dist: feet Direction: Dist: feet Direction:
Sec: Twp: Rng:
Field Name: FLANK Field Number: 24051
Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 06/13/1981 Date TD: 06/14/1981 Date Casing Set or D&A: 06/15/1981
Rig Release Date: 06/16/1981 Per Rule 308A.b.

Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

Total Depth MD 4795 TVD** Plug Back Total Depth MD 4773 TVD**
Elevations GR 3797 KB 3797 Digital Copies of ALL Logs must be Attached per Rule 308A

List Electric Logs Run:
IND, SON, TEMP

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	1,467	780	0	1,467	
1ST	7+7/8	5+1/2	15.5	0	4,792	1,125		4,795	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 06/13/1981

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
SQUEEZE	1ST	4,023	150	1,523	4,023

Details of work:

07/18/81: Squeezed perforations from 4,019'-4,023' with 150 sx Class H cement.

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
TOPEKA	2,986				
VIRGIL	3,256				
CHEROKEE	4,182				
MORROW	4,597				

Operator Comments:

This Form 5 is being submitted in response to a July 26, 2018 data request for a new Drilling Completion Report for wells that have not had one filed since 1999.

There are no cementing tickets available for this well.

This well is a re-entry of the Monsanto Chemical Company's Beth #1 well which was completed as a dry hole on December 22, 1962.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Anthony P. Trinko

Title: Sr. Reservoir Engineer Date: 5/30/2019 Email: anthony_trinko@kindermorgan.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
	CMT Summary *	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Directional Survey **	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
402048876	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402048882	PDF-TEMPERATURE	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402049491	WELLBORE DIAGRAM	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineering Tech	List of all logs run was edited Populated surface string cement top & bottom per WBD Corrected 1st string cement bottom to TD Populated remedial squeeze work date, perf depth, cement top, & bottom per WBD	09/18/2019

Total: 1 comment(s)

