

**FORM
5**Rev
10/14**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402064666

Date Received:

06/05/2019

DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 18600

Contact Name: Anthony Trinko

Name of Operator: COLORADO INTERSTATE GAS COMPANY LLC

Phone: (719) 520-4557

Address: P O BOX 1087

Fax:

City: COLORADO SPRINGS State: CO Zip: 80944

Email: anthony_trinko@kindermorgan.com

API Number 05-009-05067-00

County: BACA

Well Name: FLANK

Well Number: 7

Location: QtrQtr: SESE Section: 5 Township: 34S Range: 42W Meridian: 6
FNL/FSL FEL/FWL

Footage at surface: Distance: 660 feet Direction: FSL Distance: 660 feet Direction: FEL

As Drilled Latitude: 37.107299 As Drilled Longitude: -102.183565

GPS Data:

Date of Measurement: 09/23/2009 PDOP Reading: 3.3 GPS Instrument Operator's Name: G.H. Jarrell

FNL/FSL

FEL/FWL

** If directional footage at Top of Prod. Zone Dist: feet Direction: Dist: feet Direction:
Sec: Twp: Rng:

FNL/FSL

FEL/FWL

** If directional footage at Bottom Hole Dist: feet Direction: Dist: feet Direction:
Sec: Twp: Rng:

Field Name: FLANK

Field Number: 24051

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 12/16/1962 Date TD: 01/02/1963 Date Casing Set or D&A: 01/02/1963

Rig Release Date: 01/03/1963 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☒ Storage ☐ Observation

Total Depth MD 4738 TVD** Plug Back Total Depth MD 4153 TVD**

Elevations GR 3732 KB 3732

Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

IND, SON

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	1,373	560		1,373	
1ST	7+7/8	2+7/8	6.5	0	4,197	360	2,288	4,197	CALC
OPEN HOLE	7+7/8			4197	4,738				

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
STONE CORRAL		1,425			
NEVA	2,594				
WABAUNSEE	2,884				
TOPEKA	2,924				
LANSING	3,505				
MARMATON	3,840				
CHEROKEE	4,061				
ATOKA	4,298				
MORROW	4,456				

Operator Comments:

This Form 5 is being submitted in response to a July 26, 2018 data request for a new Drilling Completion Report for wells that have not had one filed since 1999.

There are no cementing tickets available for this well.

The Temperature Survey run by the original operator on January 3, 1963 is not available.

This well is a re-entry of the Horizon Oil & Gas Company's Government #1-5 well which was completed as gas well in January 1963.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Anthony P. TrinkoTitle: Sr. Reservoir Engineer Date: 6/5/2019 Email: anthony_trinko@kindermorgan.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
	CMT Summary *	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Directional Survey **	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
402064666	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402064968	WELLBORE DIAGRAM	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineering Tech	Added OH field per WBD Corrected 1st string status from CBL to CALC, per TEMP log (not available)	09/19/2019

Total: 1 comment(s)

