




OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



OIL & GAS
CONSERVATION COMMISSION

Dr# 123-05504

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator The Pure Oil Company Field West Buckingham Wilcat
Lease Name H. H. Duell "B" Well No. 1 County Weld
Location NW SE Section 25 Township 8-N Range 60-W Meridian 6th P.M.
(Quarter Quarter)
1980 feet from South Section line and 1980 feet from East Section Line
N or S E or W

TOTAL DEPTH 6948' DATE OF PLUGGING January 10, 1959

DETAILS OF WORK

Shot 5-1/2" OD casing at 4870'. Recovered total of 148 joints 5-1/2" OD casing - 4914'.

Plugged as follows:

Filled hole with gravel, 6866' to 6830'.
5 sacks cement at perforations. (Perforations at 6815' to 6830'.)
10 sacks cement in bottom of 8-5/8" OD surface casing at 133'.
5 sacks cement in top of 8-5/8" OD surface casing, 3' below ground level.
Heavy drilling mud between cement plugs.

Left total of 122' of 8-5/8" OD surface casing in well and 2002' of 5-1/2" OD casing in well, including threads.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	



I/~~we~~ hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Company The Pure Oil Company Date January 20, 1959

Date

JAN 21 1959

Address 1700 Broadway

Phone No AMherst 6-3337

Division Chief

By

Th. Hachburten
(Signature)

Title Production Clerk

Director

A. J. J. J.

P + a oil well