



COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS

RECEIVED  
MAR 14 1955

OIL & GAS CONSERVATION COMMISSION not reg.

(Indicate nature of data by checking below)

- Notice of intention to drill (attach plat) XXXXX
- Notice of intention to change plans \_\_\_\_\_
- Notice of date for test of water shut-off \_\_\_\_\_
- Report on result of test of water shut-off \_\_\_\_\_
- Notice of intention to re-drill or repair well \_\_\_\_\_
- Notice of intention to clean out well \_\_\_\_\_
- Statement of shooting \_\_\_\_\_
- Statement of perforating \_\_\_\_\_
- Notice to pull or otherwise alter casing \_\_\_\_\_
- Notice of intention to abandon well \_\_\_\_\_
- Report of work done on well since previous report \_\_\_\_\_

Locate Well Correctly

		3	

Notice to do work  Land: Fee and Patented   
 Report of work done  State  Lease No. \_\_\_\_\_

Colorado State Logan County Divide Field

4 (Well No.) Duncan (Lease) C. SE NE 3 8N 53W 6th  
 (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 1980 Ft. ~~(N)~~ of Section Line and 660 Ft. ~~(E)~~ of Section Line. (S) (W)

The elevation above sea level is To be submitted later. Ft.

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

We propose to drill a well, using rotary tools, on the above described location to be known as Duncan #4.

It is expected that approximately 120' of 8-5/8" OD, 10V. thd., 28.00#/ft., of surface pipe will be run and cemented to the surface. The well will be drilled to the "D" sand of the Dakota formation, which is expected at approximately 4800'KB.

If commercial production is encountered, a production string consisting of 5-1/2" OD, 8R. thd., J-55, 14#/ft. casing will be run and set on top of the producing formation and cemented with 100 sacks of cement.

AJJ	
DVR	
FJK	
OPS	
HHM	
AH	
JJD	Approved: <u>MAR 14 1955</u>
FILE	

All measurements will be taken from the top of the Kelly Bushing.

R. J. Gersin  
 Director

Date March 9, 1955

Company Trigood Oil Company  
P. O. Box 1689  
 Address Casper, Wyoming

By J. L. Fusselman  
 J. L. Fusselman,  
 Title Assistant Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.