




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

Notice of intention to drill (attach plat) ☒
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____

Locate Well Correctly

	3		

Notice to do work ☒
 Report of work done ☐

Land: Fee and Patented ☒
 State ☐

Lease No. _____

Colorado State Logan County Minta West Field

2 (Well No.) Tetsell (Lease) 8-5/8" clog in localing NE 3 8N 53-W 6th
 (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 4600 Ft. (N) of Section Line and 1999 Ft. (W) of
 Section Line.

The elevation above sea level is _____ Ft. To follow

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

Tetsell Well #2

As indicated by the above shown location, we submit this report for your approval
 to drill this well with rotary equipment and completing using the following
 general methods.

Approximately 100' of 8-5/8" O. D., 28# casing as surface string, will be landed and
 cemented to bring adequate returns to the surface. After allowing adequate
 time for cement to set, the casing string will be tested and drilling resumed.

The well will then be taken to the Dakota 'D' Sand at an approximate depth
 of 4800'. If geological analysis indicated good producing sand structure,
 an engineered string of 5-1/2" O. D., J-55 14# casing will be landed and properly
 cemented. All measurements will be reported from Kelly bushings.

Approved: JUL 27 1955

Date July 21, 1955

Company Trigood Oil Co.

Address Box 1689, Casper, Wyo.

By J. L. Fusselman

Title J. L. Fusselman, Assnt. Mgr.

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.

AJJ	
DVR	
FJK	
OPS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	