



Midwest-Davon Oil Co.
UNION PACIFIC CORMACK #1
Logan County, Colorado

<u>FORMATION</u>	<u>TOP</u>	<u>BOTTOM</u>
Samples Start at	4000	
Soft Grey Shale	4000	4355
Buff Fine Grain Lime	4355	4365
Speckled Grey Shale	4365	4450
Pink-Buff Speckled Lm. & Shale (Niabrara)	4450	4565
Mottled Pink & Grey Lm. (Ft. Hayes Lime)	4565	4592
Grey Chalky Speckled Lime	4592	4645
Grey Shale	4645	4720
Grey Chalky Lime	4720	4740
Limey Gry. Speckled Sand	4740	4750
Grey Clauconitic Limey Sand (Codell Sand)	4750	4760
Grey Shale	4760	4925
Grey Sandy Lime	4925	4950
Brown Crystalline Lime (Greenhorn Lime)	4950	4960
Sandy Lime & Shale	4960	4990
Grey Shale	4990	5030
Buff Sandy Lime	5030	5050
Grey Shale	5050	5162
Brown Lime	5162	5167
Grey Shale	5167	5192
"D" Sand	5192	5245
Grey Shale	5245	5313
"J" Sand	5313	5370
Skull Creek Shale	5370	5384
Total Depth		5384

NW NW SW Section 23-12N-53W