


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

00268104

PLUGGING RECORD

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Trigood Oil Company Field E. Buckingham Wildcat
Lease Name State Land Sec. 36 Well No. 1 County Weld
Location SW-SW-SE Section 36 Township 8-N Range 59-W Meridian 6th
(Quarter Quarter)
330 feet from So. Section line and 2310 feet from East Section Line
N or S E or W

Approved 12/16/57

TOTAL DEPTH 6579'DATE OF PLUGGING 1-1-58

DETAILS OF WORK

The above described well was plugged and abandoned on January 1, 1958, in the following described manner:

Total Depth - 6579'

Plug No. 1 - 6579'-6379' - 25 sacks of cement
6379'-6140' - Heavy Drilling Mud (6140' of 5-1/2" O.D.
14# J-55 casing recovered)

Plug No. 2 - 6140'-6060' - 10 sacks of cement
6060'-180' - Heavy Drilling Mud

Plug No. 3 - 180'-161' - 10 sacks of cement
161'-10' - Heavy Drilling Mud

Plug No. 4 - 10'-0' - 5 sacks of cement

A regulation abandonment marker has been secured over the well site, and the location has been leveled and cleared of debris.

well	site,
DVR	
WRS	
HHA	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

14 oil
counted 4-12-16-57

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Company TRIGOOD OIL COMPANY Date 12-3-59Date DEC - 4 1959Address Box 1571 - Casper, Wyo Phone No. 2-1541

Director

By J. L. Fuschman Title Mgr., Operations
(Signature)

R