



OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED
JAN 8 1957
OIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator The British-American Oil Producing Company Field West Peetz Wildcat
Lease Name Schwake Well No. B-1 County Logan
Location SW SE Section 31 Township 12N Range 52W Meridian 6 P.M.
(Quarter Quarter)
990 feet from South Section line and 1650 feet from East Section Line
N or S E or W

TOTAL DEPTH 5320'KB DATE OF PLUGGING 12-13-56

DETAILS OF WORK

Shot casing off at 3925'. Recovered 13 1/2 joints 5-1/2", 15.5# casing. Set rock bridge at 230'KB; spotted 5 sax cement from 230' to 200'; heavy mud to 35', rock bridge at 35' with 10 sax cement in top of surface casing. Erected marker, filled cellar with soil and abandoned location.

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JAN 8 1957

Director

A. J. Gervin

Company The British-American Oil Producing Company Date 12-28-56
P. O. Box 180
Address Denver, Colorado Phone No. AC2-9401
By *Thomas C. Hagan* Title Dist Supt.
(Signature)

pta oil well