



00241384

PLUG AND ABANDONMENT PROGNOSIS
DIVIDE WATERFLOOD UNIT
UNIT NO. WI-7



OIL & GAS
CONSERVATION COMMISSION

PERTINENT DATA:

ELEV: 4124 KB
KB-CHF: 8' ?
T.D.: 4967'
CASING: Sfc csg - no record
5 1/2" (14#) at 4967'

AFE: R-7066
FBTD: 4785'

PROPOSED WORK:

1. Pull injection equipment.
2. Locate 5 1/2" csg free point. Shoot off and recover.
3. Spot the following cement plugs:
 - (a) 40 sx across Muddy at 4753'.
 - (b) 30 sx across casing stub.
 - (c) 30 sx across bottom of sfc csg.
 - (d) 10 sx at sfc.
4. Install abandonment marker.
5. Fill out attached form and mail to Division Exploitation Engineer.

D. B. O'Neill

C. L. Creager

R
RHR/djc
2-23-66
Denver, Colorado