



00241321

RECEIVED

MAR 25 1969

COLO. OIL &amp; GAS CONS. COMM.

OPERATOR: A. T. Skaer, 920 Patterson Building, Denver, Colorado 80202  
 WELL: TETSELL D-1  
 LOCATION: W/2 SE/4 (1272' N/S and 2040' W/E) Section 32, T9N, R53W,  
 Logan County, Colorado  
 ELEVATION: 4143.7' G.L., 4152' K.B.  
 DATE STARTED: January 14, 1969  
 SURFACE CASING 8-5/8" at 89'  
 CORE: None  
 DRILLSTEM TEST: "J" sand 4930-38'  
 LOGS: Micro Log - surface to TD  
 Radioactivity - surface to 4627'  
 DRILLING CONTRACTOR: Exeter Drilling Company  
 STATUS: Completion in "D" sand

## Log Tops:

Formation	Depth
Bentonite	4728'
"D" Sand	4820'
"J" Sand	4928'
Total Depth	4996'

## Drillstem Tests:

DST #1: 4930-38' (straddle test "J" sand)  
 Open 60 minutes, shut-in 30 minutes, weak blow throughout  
 test. Recovered 150' gas in drill pipe, 65' muddy water.  
 Pressures:

IH	2613#
IF	16#
FF	33#
SIP	677#
FH	2602#

Will run production casing to complete in "D" sand.

6