


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



OIL & GAS
CONSERVATION COMMISSION



PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Consolidated Oil & Gas, Inc. 19650 Field Mt. Hope East "D" Wilcat
Lease Name Tetsell Well No. 1 County Logan
Location NW SE Section 32 Township 9N Range 53W Meridian 6th Princ.
(Quarter Quarter)
1980 feet from S Section line and 1980 feet from E Section Line
N or S E or W

TOTAL DEPTH 4974 PB 4942 DATE OF PLUGGING 2/12/62

DETAILS OF WORK

Fill with 130 gal. of pea gravel to 4820'. Dump 15 sack cement plug on top of gravel. Top of plug at 4690'.

Shot 5 1/2" casing at 3896' and pulled. Plug bottom of surface pipe with 10 sacks cement. Plug top of surface pipe with 5 sacks cement.

Work done by Rocket Oil Well Servicing Co., Box 4748, Denver, Colorado.

*11/9/62 Loc. Leveled.
Hm*

Proved

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date MAR 22 1962

G. J. Gessin
Director

Company Consolidated Oil & Gas, Inc. Date March 20, 1962

Address 2112 Tower Bldg., Denver Phone No. AM 6-1306

By *[Signature]* Title Chief Engineer

(Signature)

VIOLATION

REMARKS- *Lat*

T