

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400495187

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 69175

2. Name of Operator: PDC ENERGY INC

3. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

4. Contact Name: Cassie Gonzalez

Phone: (303) 860-5800

Fax:

Email: Cassie.Gonzalez@pdce.com

5. API Number 05-123-36023-00

7. Well Name: Simonsen

8. Location: QtrQtr: NWNW Section: 12 Township: 6N Range: 67W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

6. County: WELD

Well Number: 12E-223

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 02/25/2013 End Date: 02/25/2013 Date of First Production this formation: 03/11/2013
Perforations Top: 7582 Bottom: 11548 No. Holes: Hole size:

Provide a brief summary of the formation treatment:

Open Hole: ☒

16 Stage Sliding Sleeve, Swell Packer set at 7,582'

Total Fluid: 58,263 bbls

Gel Fluid: 47,058 bbls

Slickwater Fluid: 11,205 bbls

Total Proppant: 3,300,206 lbs

Silica Proppant: 3,300,206 lbs

Method for determining flowback: measuring flowback tank volumes.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 58263

Max pressure during treatment (psi): 4052

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 8.34

Type of gas used in treatment:

Min frac gradient (psi/ft): 0.96

Total acid used in treatment (bbl):

Number of staged intervals: 16

Recycled water used in treatment (bbl):

Flowback volume recovered (bbl): 40

Fresh water used in treatment (bbl): 58263

Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 3300206

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 04/03/2013 Hours: 24 Bbl oil: 159 Mcf Gas: 896 Bbl H2O: 23
Calculated 24 hour rate: Bbl oil: 159 Mcf Gas: 896 Bbl H2O: 23 GOR: 5635
Test Method: Flowing Casing PSI: 966 Tubing PSI: 641 Choke Size: 16/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1362 API Gravity Oil: 45
Tubing Size: 2 + 3/8 Tubing Setting Depth: 7130 Tbg setting date: 03/08/2013 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Cassie Gonzalez

Title: Regulatory Technician Date: Email: Cassie.Gonzalez@pdce.com

Attachment Check List

Att Doc Num Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Returned to draft for AOC settlement.	09/15/2016
Permit	Form 5 is missing directional survey. Opr notified and I am waiting for all the information prior to passing this 5A	04/15/2014
Permit	No field name, no summary of the formation treatment and the GOR is incorrect. Opr notified.	12/31/2013

Total: 3 comment(s)