




OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



PLUGGING RECORD

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator British-American Oil Producing Company Field S.E. Padroni Wildcat

Lease Name GIACOMINI Well No. B-1- County Logan

Location NE SE Section 26 Township 9N Range 52W Meridian 6PM
(Quarter Quarter)

2016 feet from South Section line and 697 feet from East Section Line
N or S E or W

TOTAL DEPTH	<u>4687' KB</u>	DATE OF PLUGGING	<u>5-1-58</u>
-------------	-----------------	------------------	---------------

DETAILS OF WORK

Ran Drill Pipe open-ended, filled hole with heavy Rotary mud to 4475, spotted 50 sax cement plug from 4475 to 4317, heavy mud to 180, 15 sax cement plug in bottom of surface casing from 180 to 160, heavy mud from 160 to 16, 10 sax cement plug from 16 to within cellar, erected marker, levelled and abandoned location.

AJJ	
DVR	
WRS	<input checked="" type="checkbox"/>
HMM	
JMM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: _____ Date MAY - 7 1958

Company British-American Oil Date 5-6-58

Address Box 180, Denver 1, Col Phone No. AC 2 9401

Director *Affirm* By *Thomas M. Boyd* Title Dist. Supt
(Signature)