


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

00254964

PLUGGING RECORD



INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

ALLISON-ZION SUPPLY COMPANY AGENT FOR W.C. McBRIDE Field PADRONT Wildcat

Lease Name STATE Well No. "D" County LOGAN

Location C SWNE (Quarter Quarter) Section 16 Township 9N Range 52W Meridian 6

2022 feet from N Section line and 1972 feet from E Section Line
N or S E or W

TOTAL DEPTH 4778, PB4570DATE OF PLUGGING 11/14/63

DETAILS OF WORK

1. RAN SAND TO 4500'
2. DUMPED 5 SAX CEMENT TO 4462'
3. SHOT CASING @ 3620' & 3500'
4. MUD HOLE TO 190'
5. ROCK BRIDGE TO 187'
6. DUMPED 10 SAX CEMENT TO 165'
7. MUD TO 12'
8. RUN 5 SAX CEMENT TO BASE CELLAR
9. CUT OFF SURFACE PIPE, BOTTOM OF CELLAR AND WELD ON CAP.

10/22/64 Checked loc. OK

Hm

Ex
GTS
Prod.

DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date

NOV 21 1963

Director

ALLISON-ZION SUPPLY COMPANY

Company

Date 11/20/63

715 WESTERN FEDERAL SAVINGS BUILDING

Address

Phone No. 825-2355

By

AVERY BROWN

(Signature)

Title MANAGER