

Donnelly Casing Pulling Co.

Phone 522-1410

P.O. Box 791
Sterling, Colorado 80751

Bob Donnelly

SOLD
TO

Romac Exploration Co.
4 Waring Lane
Littleton, CO 80121



INVOICE DATE 1-17-94

WELL

Houston
Hudson #1-20

INVOICE NO. 94-094

Pulled tubing and casing;
plugged well:

\$1000.00

Hauled tubing and casing to
Allen & Schramm's yard:

Mack Truck, 7 hours @
Trailer, 7 hours @
Helper, 7 hours @

\$50.00 per hor
\$10.00 per hour
\$18.00 per hour

350.00
70.00
126.00

TOTAL

\$1546.00

BELOW IS FOR INFORMATION ONLY

Day Work, 50 hours @
Cement, 80 sacks @

\$90.00 per hour
\$ 8.00 per sack
tax

\$4500.00
640.00
19.20

Shots, 2 @

\$40.00 per shot

80.00

Pump Job, 1 @

\$500.00 per job

500.00

Water Truck, 6 hours @

\$40.00 per hour

240.00

Welder, 3 hours @

\$21.00 per hour

63.00

\$6042.20

DATE DAY WORK

REMARKS

1-03-94 10 hours

Moved rig. Raised mast. Rigged up tongs.
Unseated anchor. Pulled 2000' tubing.

1-05-94 10 hours

Pulled rest of tubing. Ran sand from 4648'
to 4550'. Dug cellar. Water truck, 3 hours,

1-06-94 10 hours

Rigged up jacks. Dumped 5 sacks cement on sand
at 4550'. Worked pipe to 35".

1-10-94 10 hours

Worked pipe. Ran shots to 4000' and 3600'.
Worked loose. Pulled 60 joints.

1-11-94 10 hours

Pulled rest of casing. Ran tubing to stub.
Pumped 35 sacks cement. Pulled tubing to bottom
of surface. Pumped 35 sacks in and out bottom
of surface. Pulled tubing. Set 10 sacks cement
in top. Cut off and welded on cap. Water truck,
3 hours.

WELL COMPLETE

THANK YOU