




99999999

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



OIL & GAS
CONSERVATION COMMISSION

075 06371

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator TEXACO Inc. Field Padroni Wildcat
Lease Name D. E. Gould Well No. 2 County Logan
Location SW SW SE Section 20 Township 9N Range 52W Meridian 6th PM
(Quarter Quarter)
330 feet from South Section line and 2970 feet from West Section Line
N or S E or W

TOTAL DEPTH 4746' KB DATE OF PLUGGING Feb. 4, 1966

KB Elev - 3975' Gr Elev - 3963'

DETAILS OF WORK

Above described well was plugged and abandoned as follows:

- 1) Plug No. 1 - 30 sx cement - 4518-4725'KB - Across perforations
- 2) Shot casing at 4008', 3708' and 3601'KB. Parted casing at 3490' KB. Pulled casing.
- 3) Plug No. 2 - 25 sx cement - 194-114'KB - Bottom of surface casing
- 4) Plug No. 3 - 8 sx cement - 2'-15' Gr - A cap was welded on top of the surface casing.

NOTE: 9.5# mud was spotted between plugs

1255' of 5-1/2" OD 15.5# casing - Interval 4745-3490'KB - and 155' of 10-3/4" OD 32.75# casing - surface casing 2'-157' Gr - were abandoned in the hole.



00818120

DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

EX
Oil
Prod

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date FEB 16 1966

Director

DRA-LNF
COGCC (2) RW DCB DRA BSMcP

Company TEXACO Inc.

P.O. Drawer 740
Address Casper, Wyoming

By [Signature] (Signature)

Date Feb. 11, 1966

Phone No 234-5353
District

Title Superintendent

was cut & gas - ended up as oil