



YETTER WELL SERVICE, INC.

Drawer 1808 / 15504 Highway 14 / Phone 303 522-2885
Sterling, Colorado 80751

July 19, 1989

INTERMOUNTAIN OIL CO.
P O BOX 897
NIWOT, CO 80544

COPY

Lease: Walters #1
Rig: 9
WO: R. Grimmette

7-17-89 Moved rig and equipment to location and rigged up.
Set up to work casing. Unlanded casing and worked
it free. Dumped 130 gal. of 1/2" rock down hole.
Ran casing jars to make sure rock went to bottom.
Loaded hole and pressured to 500 psi. Rigged up
Bran-Dex Wireline truck. Mixed and spotted five
sacks of cement on top of rock at 4918' with dump
bailer.

8 hours

7-18-89 Worked casing and set up Bran-Dex. Shot off casing
at 4120'. Pulled and laid down casing on float.
Picked up tubing and ran it to bottom of surface.
Spotted 25 sacks of cement to plug half in and half
out of surface. Pulled tubing out and plugged sur-
face with five sacks of cement. RDMO.

11 hours

TOTAL 19 HOURS



Unit Charge, 19 hours, @ \$100.00	-----	\$1900.00
Casing Tools	-----	100.00
35 Sacks Cement	-----	250.25
Mud Pump and Circ. Tank (trucking included)	---	400.00
Extra Labor, 11 hours, @ \$14.00	-----	154.00
1 Ton Truck, 3 hours, @ \$25.00	-----	75.00
Tandem-Axle Truck & Float, 2 hours, @ \$57.00	--	114.00

TOTAL \$2993.25

RECEIVED

AUG 07 1989

THANK YOU, WE DO APPRECIATE YOUR BUSINESS!

TERMS: NET 30 DAYS 18% Annual Finance Charge (1.5% Per Month)

SOLO.OIL & GAS CONS.COMM.

Sterling, CO 80751

Company Intermountain Oil Co

Date July 18-89

By _____

Customer No. _____

Address

Address _____
Well Intermountain Waters #1 County Logan State Co

Field _____ Location _____

[illegible]

PAID
1462 7/31/89
CK NO. DTE

RECEIVED

AUG 07 1989

COLO. OIL & GAS CONS. COMM.

TOTAL	1300
-------	------