

KP KAUFFMAN

AMOCO Champlin 117-I-2

NWSE SEC 21, T2S, R66W

Current Completion

API #: 05-001-6233

KB Elev.: 5236'

GL Elev.: 5225'

KB = 11'

9-5/8", 40#, K55 Casing @ 1675'

Tubing: 2-7/8", 6.5#, J55, 276 jts

Anchor ~ 8283'

Plunger lift

Plunger lift spring

SN ~ 8411'

String bottom ~ 8438'

PBTD ~ 8435'

8368'-8384'(16'), 4jspf, 64js

8394'-8412'(18'), 4jspf, 72js

5-1/2" 17#, J55 @ 8535'

D-Sand ~ 8320'

J-Sand ~ 8356'

Drawn by

jfmc

2/13/2004