

Crumley Pumping Service, LLC

PO BOX 475
Akron, CO 80720
Cell (970) 768-5659

November 4, 2019

PADCO, LLC
800 W, 6th Street
Los Angeles,

Suite 1010
CA 90017-2713

Invoice for plugging supervision on Wright #1D

10/19/2019 - LLG roustabouts broke out treater at tank battery, hauled it off for junk

10/21/2019 - Yetter tested anchors, put in 2 new. LLG roustabouts dug up well head, tested Braden head, no pressure or fluid on Braden head, no pressure or fluid on tubing or casing. Yetter rigged up on well, pulled rods, laying down 62 - 7/8", 106 - 3/4" on trailer, pulled 152 jts 2 3/8" tubing to derrick. Yetter delivered plugging equipment to location (cementing unit, triplex pump & 2 swab tanks) S&S delivered 75 bbls water.

10/22/2019 - Susan w/ COGCC, Brand X on location, set CIBP @ 4725' mix & dump 2 sx cement on top of plug
LLG roustabouts welded straps on casing collar
S&S delivered 75 bbls water and standby with vac truck
run tubing in, tallying, mix and pump 20 sxs gel, circulate hole clean
pull tubing, stand 96 jts in derrick, lay down 56 jts
S&S cleaned swab tank
unland casing, work pipe, getting 14" of stretch @ 80,000#.

10/23/2019 - E3 Solutions delivered 100 bbls fresh water
Yetter start working casing, 15.5" stretch @ 80,000#, 22" stretch @ 100,000#
Susan w/COGCC on location, Susan called Dirk Sutphin, he gave permission to cut casing and we don't have to tag the stub plug.
Brand X on location, shoot casing off @ 2179', rig up to lay down casing, pull and lay down 67 jts 5.5" casing. run in 28 jts tubing.

10/24/2019 - pull and lay down 28 jts tubing, run 68 jts tubing (2179')
mix and pump 40 sx of 14.5# cement, pull tubing up and mix and pump 50 sx of 15# cement @ 307'. Standby 4 hours waiting for cement to harden. run in with tubing, tag plug @ 195'. Susan w/COGCC said it is OK to proceed, mix and pump 10 sx from 50' to surface. Yetter rigged down and moved off. S&S cleaned up swab tanks

10/25/2019 - cement 36" from top of surface casing, Yetter hauling off equipment

4 days @ \$300.00 per day \$1200.00

Thankyou