



00215596

Donnelly Casing Pulling Co.

Phone 522-1410

P.O. Box 791
Sterling, Colorado 80751

RECEIVED

DEC 7 1984

Bob Donnelly
COLO. OIL & GAS CONS. COMM.

SOLD TO

Classic Petroleum
c/o Mr. Robert W. Fisher
1020 15th St., Suite 10-I
Denver, Colorado 80202

INVOICE DATE 12-4-84

WELL

Graham #23-13

INVOICE NO. 85-948

THIS IS NOT AN INVOICE. FOR INFORMATION ONLY.

4773' 4½" OD Casing @	70¢ per foot	\$3341.10
Day Work, 47 hours @	\$50.00 per hour	2350.00
Cement, 60 sacks @	\$7.00 each + tax	434.70
Shot, 1 @	\$30.00 per shot	30.00
Pump Jobs, 2 @	\$550.00 per job	1100.00
Hauled pump to & from Lease:		
Mack Truck, 4 hours @	\$46.00 per hour	184.00
Water Truck, 13 hours @	\$42.00 per hour	546.00
Welder, 4 hours @	\$21.00 per hour	84.00
Vacuum Truck, 4 hours @	\$47.00 per hour	188.00
1620' 1" Tubing @	20¢ per foot	324.00
30 Bbl. Oil @	\$28.00 per bbl.	840.00
		<u>\$9421.80</u>

DATE	DAY WORK	REMARKS
10-29-84	10 hours	Moved rig on well. Raised mast. Hooked up lines. Dug cellar. Checked in at 6720'.
10-30-84	10 hours	Ran sand to 6700'. Set in jacks. Worked pipe to 10". Started running tubing. Loaded hole. Water truck, 7 hours.
10-31-84	10 hours	Ran 50 joints tubing, total. Soptted 30 bbls. oil. Water truck, 6 hours. Vacuum truck, 4 hours. Pump job.
11-1-84	9 hours	Dumped 5 sacks cement on sand at 6700'. Worked pipe to 40". Shot at 4800'. Worked loose. Pulled 30 joints.
11-2-84	8 hours	Pulled 60 joints casing. Pumped 25 sacks cement at 1200'. Pulled rest of casing. Pumped 20 sacks cement at 275'. Mudded to 28'. Set 10 sacks cement to base of cellar. Welded on cap. Pump job.

WELL COMPLETE

THANK YOU