




00241435

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

(Indicate nature of data by checking below)

Notice of intention to drill (attach plat) _____
Notice of intention to change plans _____
Notice of date for test of water shut-off _____
Report on result of test of water shut-off _____
Notice of intention to re-drill or repair well _____
Notice of intention to clean out well _____
Statement of shooting _____
Statement of perforating _____
Notice to pull or otherwise alter casing _____
Notice of intention to abandon well _____
Report of work done on well since previous report _____
Notice of abandoning well ☒

Locate Well Correctly

		o	
	35		

Notice to do work ☒
Report of work done ☐

Land: Fee and Patented ☒
State ☐

Lease No. _____

Colorado
State
TRUE AND BROWN, R. H. FULTON,

Logan
County

Wildcat
Field

WAGNER #1 Fee NW NW NE 35 9 North 53 W 6th PM
(Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 330 Ft. ~~(N)~~ of Section Line and 2310 Ft. ~~(E)~~ of
(S) (W)
Section Line.

The elevation above sea level is 4156 Ft. KB 4166'

Details of Plan of Work: (State names of and expected depths to objective sands.
Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
points, and all other important proposed work.)

The subject well was drilled to a depth of 4930 feet with no indication of oil or gas
being found. 8-5/8" casing was cemented at 98 feet with 50 sax of cement. The well was
plugged and abandoned June 8, 1955 in the following manner:

Plug #1, 38 sax at 4750' (calculated to fill to 4850')

Plug #2, 15 sax at 98', base of surface pipe

Plug #3, 5 sax top of surface.

The hole was full of drilling mud which weighed 10.0 lbs per gallon and had a viscosity
of 95 seconds.

This confirms the telephone conversation with your office by our Mr. L. E. Bludworth.

2 copies of Electric Log are attached.

Approved: JUN 13 1955

[Signature]
Director

AJJ	
DVR	
FJK	
OPS	
HMM	
AH	
JJD	

Date June 8, 1955Company TRUE OIL COMPANYAddress P. O. Box 203, Casper, Wyo.By *[Signature]*Title Partner

Submit reports of proposed work, for approval, on this form in Duplicate for patented
lands and in Triplicate for school and state lands.
cc:GH, RHF, DSB