




COLORADO OIL CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

OIL & GAS
CONSERVATION COMMISSION

Locate Well Correctly

- Notice of intention to drill (attach plat) _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of ~~intention to~~ abandon well _____
- Report of work done on well since previous report _____

		35	
			o

Notice to do work Land: Fee and Patented
 Report of work done State Lease No. Wagner

Colorado State Logan County Wildcat Field
 TRUE OIL CO., R. H. FULTON,
 WAGNER #3 Fee SE SE SE Sec. 35 9 N 53 W 6th P.M.
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 330 Ft. (N) of Section Line and 330 Ft. (E) of Section Line.

The elevation above sea level is 4147* Ft. Gr.

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

The above described well was drilled to a total depth of 4962 feet and did not encounter any commercial quantities of oil or gas. An electric log was run to the total depth and the well was plugged September 27, 1955, in the following manner:

- Plug #1, 4920' to 4790' - 40 sax - covering the D and J Sands
- Plug #2, 120' to 71' 25 sax
- Plug #3, 5 sax in the top of the surface casing

The surface casing was new 10-3/4" landed at 97.50' with 60 sax of cement.

The hole was full of drilling mud having a weight of 10 #/gal. and a 55 sec. viscosity.

Two copies of the electric log will be forwarded as soon as they are received.

AJJ	
DVR	
FJK	
OPS	
HMM	
AM	
JJD	

Approved: SEP 28 1955

Date September 27, 1955

A. J. Jensen
Director

Company TRUE OIL COMPANY

Address P. O. Box 1612, Casper, Wyoming

By *[Signature]*

Title Partner

cc:RHF, GH

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

T