

**OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO**



00202306



UNDY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompletion ☐Notice of Intention to Abandon Well ☐Other Report of work done on well ☒

(Check appropriate space) since previous report

LEASE NAME USA-S. Marvin James WELL NO. 1

FIELD Curtis Anticline WILDCAT Yes COUNTY Routt

LOCATION NE NE NE Section 25 Township 6N Range 86W Meridian 6th PM
(Quarter Quarter)

334 feet from S Section Line and 334 feet from W Section Line
N or S E or W

(DETAILS OF WORK)

Ran 102 jts. 7-5/8" O.D., 26.4#, N-80 Spang Xline std. jt. casing. Total 4082'. Set at 4094' with 72 sacks regular cement with 2% CaCl₂. Drilled 6-3/4" hole to 5620'. Ran Schlumberger logs (see below). Plugged back to 4800' as follows: 50 sacks regular cement 5330-5550', and 75 sacks regular cement 4800-5035', leaving open hole from 4094' to 4800'.
Ran 130 jts. 2-3/8" O.D., EUE, 4.7#, J-55 tubing. Total 4107'. Set at 4116' K.B. Seating nipple at 4047'. Ran rods and 1-1/2" pump. Constructed tank battery and potentialied well 1-27-58. IP: Pumped 187 BOPD 1% BS&W, 17-54" SPM, GOR 600:1, 1-1/2" pump. Producing formation: Niobrara Shale.

Logs: ES - 4505-358
ES Induction - 5615-4092
ML - 4505-358
GRN - 4506-325

AJJ	
DVR	
WRS	
HHM	
JAM	✓
FJP	✓
JJD	✓
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

APR 23 1958

Date

Director

Company Tennessee Gas Transmission Co Date February 25, 1958Address P. O. Box 1772, Casper, Wyo Phone No. 2-3501By Patterson Lay Title District

(Signature)

Superintendent

682