


OIL AND

00544919

COMMISSION

STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompletion ☐Notice of Intention to Abandon Well ☐Other - Salvage Casing ☒

(Check appropriate space)

LEASE NAME John Thams, Jr. WELL NO. 1FIELD Curtis WILDCAT - COUNTY RouttLOCATION C-SW-NE Section 25 Township 6N Range 86W Meridian 6th
(Quarter Quarter)2025 feet from N Section Line and 2003 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

A previous request was filed for permission to abandon this well with the Production Casing in the hole. Due to the need for the casing and other considerations; We are now asking for a revocation of that request in favor of a permanent abandonment. -

Plugging Procedure as follows:

Plug at 4065' w/ 10 sxs cement in 7" casing.

Cut 7" casing at approximately 3300'

Pull 7" casing.

Plug at 1474' w/ 40 sxs. cement in 9-5/8" surface casing.

Dump 5 sxs cement in top of surface casing and erect dry hole marker.

Well Data:

TD ~~4065~~ 4811'

PBTD 4468

7" casing set at 4065'

9-5/8" casing set at 1474'

Top of Cement at 3400' (Temperature Survey)

Top of Niobrara at 3679'

FILE	
JD	
FP	
JAN	
WAS	
DVR	

Agents	
Bond	
Spot	
600 ft.	
1200 ft.	
Wells	
Oil	
Gas	
Status	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

Tennessee Gas

APPROVED:

Company Transmission Co. Date 11-29-58Date DEC - 1 1958Address Box 1772, Casper, Wyoming Phone No. 2-3501Director A. J. GermainBy (Signature) Patterson Lay Title District Superintendent