



00544937

7-16-56 Drilling 890' hard sand  
7-17-56 Drilling 898'  
7-18-56 Drilling 907'  
7-19-56 Drilling 914' hard sand  
7-20-56 Drilling 930'  
7-23-56 Drilling 970'  
7-24-56 Drilling 977'  
7-25-56 Drilling 997'  
7-26-56 Drilling 1006'  
7-27-56 Drilling 1015' sandy shale  
7-28-56 Drilling 1030'  
7-29-56 Drilling 1065' dark shale  
7-31-56 Drilling 1092' sandy shale and sand  
8-1-56 Drilling 1101' hard fine sand  
8-2-56 Depth 1113'. Stuck bailer at 1090' and broke sand line,  
fished out bailer.  
8-3-56 Drilling 1130', sand, slight oil show.  
8-4-56 Drilling 1147'  
8-6-56 Drilling 1165' hard fine sand  
8-7-56 Drilling 1181'  
8-8-56 Drilling 1190' hard fine sand  
8-10-56 Depth 1208' Ran Schlumberger log  
8-11-56 Reaming 10" hole at 820'  
8-15-56 Reaming at 1082'  
8-21-56 Reaming at 1192'  
8-23-56 Depth 1208' waiting on new rig to run 8 5/8" casing  
9-10-56 Rigged up new string cable tools. Cleaned out hole.  
Running 8 5/8" casing  
9-13-56 Drilling 1250'. Landed 8 5/8" casing at 1207' mudded up  
behind casing.  
9-14-56 Drilling 1340'  
9-17-56 Drilling 1565'  
9-18-56 Drilling 1630'  
9-20-56 Drilling 1725'  
9-21-56 Drilling 1800'  
9-25-56 Drilling 1905' shale  
9-27-56 Drilling 2010'  
10-1-56 Drilling 2180' Deviation: 2075' - 3/4  
10-10-56 Drilling 2310'  
10-12-56 Drilling 2400'  
10-15-56 Drilling 2555' slight show of gas  
10-17-56 Drilling 2647' gas did not increase  
10-18-56 Drilling 2760'  
10-19-56 Drilling 2825'  
10-22-56 Drilling 2975'  
10-24-56 Depth 2975' hole caving  
10-29-56 Depth 2975'. Attempted to pull 8 5/8" casing. Casing  
and recovered 3 joints. Top of stub about 1 foot below  
bottom of 10 3/4" casing shoe. Could not pull 8 5/8" casing  
past bottom of 10 3/4" casing shoe. Preparing to run  
11-2-56 Depth 2975' fishing for tools  
11-7-56 Depth 2975' Ran 7" casing to 2943'. Cleaning out hole to  
11-11-56 Depth 2996' Landed 7" casing at 2996'  
11-12-56 Drilling 3075' shale  
11-13-56 Drilling 3215' shale. Dev. 3215' zero  
11-14-56 Drilling 3295' shale  
11-15-56 Drilling 3360'

BEST IMAGE  
AVAILABLE