

RECEIVED
JUN 15 1959

107-05041

Budget Bureau No. 42-R356.5.
Approval expires 12-31-60.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

LAND OFFICE Denver
LEASE NUMBER 056134-A

OIL & GAS
CONSERVATION COMMISSION



LESSEE'S MONTHLY REPORT OF OPERATIONS

State Colorado County Routt Field Curtis

The following is a correct report of operations and production (including drilling and producing wells) for the month of Oct, 1957 to June, 1959, McBride #1 Water Well

Agent's address P. O. Box 1772 Company Tennessee Gas & Oil Co
Casper, Wyoming Signed PATTERSON LAY

Phone 2-6981 Agent's title District Superintendent

SEC. AND 1/4 OF 1/4	TWP.	RANGE	WELL NO.	DAYS PRODUCED	BARRELS OF OIL	GRAVITY	CU. FT. OF GAS (In thousands)	GALLONS OF GASOLINE RECOVERED	BARRELS OF WATER (If none, so state)	REMARKS (If drilling, depth; if shut down, cause; date and result of test for gasoline content of gas)
NE NE 25	6N	86W	1	-	-	-	-	-	-	MIRU Toles & Toles Contr. 7" Csg Full of mud. Pulled 7" Csg up 2 jts PB 2951-66 w/5 sxs cement. Continued pulling 7" Csg. PB 1180 - 50 w/10 sxs. cement. Continued pulling 7" Csg to 205'. TD 3470' PBTD 1150'. At this point Tenn Gas assumed operations to convert to water well. 10-2-57 RU Toles & Toles. Strung in to 822! No fluid. RU B J Services. Perf 8-5/8" from 813-825' w/ 2 shots per ft. Bail tested & Co mud. 10-3-57 Ran rods & tbg POP. Well pumped 24OBWPD. 20x32"SPM. Well did not produce sufficient quantity of water for drilling USA-James#1. Pulled rods & Tbg. Capped well Operations suspended

File

amount head

Distb:
USGS (2)
COGCC (1)
File (1)

Well data:
TD 3470' PBTD 1150'
10-3/4" Csg set at 92.1'
8-5/8" Csg set at 850'
7" Csg now hanging in hole at 205'

NOTE.—There were No runs or sales of oil; No M cu. ft. of gas sold; No runs or sales of gasoline during the month. (Write "no" where applicable.)

NOTE.—Report on this form is required for each calendar month, regardless of the status of operations, and must be filed in duplicate with the supervisor by the 6th of the succeeding month, unless otherwise directed by the supervisor.