



00208526

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

file  
RECEIVED  
JAN 13 1958

OIL & GAS  
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator BILL TOMBERLIN Field Wildcat XX  
Lease Name HILLSLAN D & CATTLE CO Well No. 1 County JACKSON  
Location C SE SE Section 32 Township 6N Range 79W Meridian 6th  
(Quarter Quarter)  
660 feet from S Section line and 660 feet from E Section Line  
N or S E or W

TOTAL DEPTH 1497 DATE OF PLUGGING 1-10-58

DETAILS OF WORK

Casing in hole: 80 feet 8 5/8 24 # New Surface cemented to surf.  
Plugs: 1497 to 100 feet ---Heavy mud( 11.3#, 180 vis.)  
100 to 80 feet 5 sxs regular cement  
80 to 50 feet 10 sxs ditto  
30 to 1 feet 10 sxs ditto  
Csing cut off 1 foot below surf.

Well temporarlily abandoned.

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	✓
FILE	

CONFIDENTIAL

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: \_\_\_\_\_ Date JAN 13 1958  
Company BILL TOMBERLIN Date 1-10-58  
Address 703 Patterson bldg, Denver, Colo. Phone No. AL 5 6648  
By Robert H. Munn Title Asst  
Director \_\_\_\_\_ (Signature)