

**FORM**  
**5**Rev  
10/14**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402224477

Date Received:

**DRILLING COMPLETION REPORT**

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100322

Contact Name: Craig Richardson

Name of Operator: NOBLE ENERGY INC

Phone: (303) 228-4232

Address: 1001 NOBLE ENERGY WAY

Fax:

City: HOUSTON

State: TX

Zip: 77070

Email: Denverregulatory@nbleenergy.com

API Number 05-123-48628-00

County: WELD

Well Name: Guttersen

Well Number: D25-753

Location: QtrQtr: SENW Section: 25 Township: 3N Range: 64W Meridian: 6  
FNL/FSL FEL/FWL

Footage at surface: Distance: 1427 feet Direction: FNL Distance: 1982 feet Direction: FWL

As Drilled Latitude: 40.199704 As Drilled Longitude: -104.502111

GPS Data:

Date of Measurement: 08/26/2019 PDOP Reading: 2.5 GPS Instrument Operator's Name: Toa Sagapolutele  
FNL/FSL FEL/FWL\*\* If directional footage at Top of Prod. Zone Dist: 193 feet Direction: FNL Dist: 2450 feet Direction: FWL  
Sec: 25 Twp: 3N Rng: 64W  
FNL/FSL FEL/FWL\*\* If directional footage at Bottom Hole Dist: 200 feet Direction: FNL Dist: 2499 feet Direction: FWL  
Sec: 13 Twp: 3N Rng: 64W  
FNL/FSL FEL/FWL

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 09/08/2019 Date TD: 09/11/2019 Date Casing Set or D&amp;A: 09/13/2019

Rig Release Date: 09/28/2019 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 17758 TVD\*\* 6753 Plug Back Total Depth MD 17693 TVD\*\* 6753

Elevations GR 4787 KB 4817

Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

MWD/LWD, (IND-GR in 123-15611)

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	36.94	0	110	64	0	110	CALC
SURF	13+1/2	9+5/8	36	0	1,918	641	0	1,918	VISU
1ST	8+1/2	5+1/2	17	0	17,740	1,835	2,393	17,740	CALC

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,727				
SUSSEX	4,098				
TEEPEE BUTTES	6,048				
NIOBRARA	6,724				

Operator Comments:

TPZ is estimated. Actual will be submitted on 5A.

As drilled GPS was surveyed after conductor was set.

Alternative Logging Program: No open hole logs run per rule 317.p. IND-GR ran on Dalbey D 25-3 (123-15611).

Noble will run the CBL prior to completing (perforating) the well. The CBL will be submitted via Sundry Notice immediately after it is run. The top of cement calculation is based on contractor's cement tickets.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Stephany OlsenTitle: Regulatory Analyst

Date: \_\_\_\_\_

Email: stephany.olsen@nblenergy.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
402247184	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
402247203	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
402247201	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402247211	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402247214	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402247215	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

