

7WL  
RECEIVED  
MAR 11 1960

OIL & GAS  
CONSERVATION COMMISSION

05096  
10740024  
99999999

4  
NWNW 17-6N-86W

Form PO-214 Sheet 2 30M 11-51

District Tow Creek Colo. Owner The Texas Company Farm Henry Dennis

Well No. 2

FORMATION

BOTTOM

AMOUNT

COLOR

HARD or SOFT

DEPTH CORES  
TAKEN

REMARKS

SUPPLEMENTAL REPORT

Started rigging up to pull casing and abandon June 16th, 1934.

Harrelson Brothers, Contractors. W. E. Harrelson, Driller, E. D. Harrelson, Tool Dresser.

Started working loose 6 5/8" casing 6-21-34. Pulled up one joint, started filling 6 5/8" hole with mud. Set plug and bridged hole at 2550'. Put in 10 sacks cement. Pulled all 6 5/8" casing, 2554'7" (over all).

Filled 8 5/8" hole with mud and bridged hole at 2025'. Put in 10 sacks cement.

Started pulling on 8 5/8" casing June 27th, but would not come out. Pulled out clamping nipple. Screwed back with steel die nipple. Filled hole with water to try to work loose. Jarred on pipe and it parted. Pulled out 1312'5" 8 5/8" (over all) Lost 668' in hole. Started jarring on 10 3/4" but it would not move. Started working below 10 3/4". Bridged hole at 900', put in 8 sacks cement. Ripped 10 3/4" at about 700 feet but it would not come out. Ripped again at about 600'. Pulled out 586'6". Lost 279' 10 3/4" in hole.

Filled 10 3/4" hole with mud. Filled 13" hole with mud. Cemented top with 2 sacks cement and put up marker. Started tearing down tools July 5th, 1934.



Signed James Steery

JK-JCL

ARW(4)-CFN

copy to ACH-OH-Arom ARW 9/24/34