



00726483

TEXAS PRODUCTION COMPANY

TOW CREEK ANTICLINE


ROUTT COUNTY, COLORADO.

Henry Dennis #2

802' S. of N. line and 220' E. of W.
line, Sec. 17, T. 6 N., R. 86 W.

Elevation 6459'

T.D. 3010'

CASING RECORD:

15 1/2"	29'
10"	865'
8 1/4"	1980'
6 1/4"	2527'

0	30	Gravel
30	110	Shale, gray, soft
110	212	Sand, " hard
212	220	Shale, dark "
220	225	Sand, " "
225	250	Shale, " med.
250	265	Sand, gray, med.
265	505	Shale, " "
505	865	" dark, "
865	880	Sand, gray, "
880	1060	Shale, " soft
1060	1450	" blue, soft
1450	1640	" gray "
1640	2055	" blue "
2055	2270	" gray "
2270	2527	" blue "
2527	2580	" gray "
2580	2675	" blue "
2675	2965	" gray "

2515' first show oil and gas

Deepened from 2675 4-17-28.
More oil from 2750-2770
500' oil in hole at 2815'
More oil from 2920-2945.

2965	3010	" dark
------	------	--------