

OFFICE OF STATE OIL INSPECTOR
 SUNDRY NOTICES AND REPORTS OF WELLS
 LOCATED ON PRIVATE LANDS



00374671

*1 approved copy
 returned 7-6-51
 LR
 151C*

(Indicate nature of data by checking below)

- Notice of intention to drill.....
- Notice of intention to change plans.....
- Notice of date for test of water shut-off.....
- Report on result of test of water shut-off.....
- Notice of intention to re-drill or repair well.....
- Notice of intention to clean out well.....
- Statement of shooting.....
- Statement of perforating.....
- Notice to pull or otherwise alter casing.....
- Notice of intention to abandon well.....
- Report of work done on well since previous report..... **X**

Following is a ~~(report of work done)~~ *(report of work done)* ~~(On land)~~ *(On land)* ~~described as follows:~~ *described as follows:*

July 2 1951

Colorado Logan Mt. Hope
 State County Field
 6 C. F. GREEN "A" SW SW NW Section 30-9N-53W
 (Well No.) (Lease) (Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian)

The well is located 330 ft. (N) of S line and 330 ft. (E) of W line.

The elevation above sea level is 4195 ft. (d.f.)

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

- 5-16-51 TD 5069 Shale. 4 1/2" csg cem @ 5065 with 250 sax.
- 5-20-51 PBSD 5006 Sand & Shale.
 Perforated 4 1/2" casing 4865 to 4894 with 116 jet charges.
- 5-21-51 Ran 2" tubing & swabbed through tubing.
- 5-23-51 Well flowing, made 146 bbls oil & no water in 24 hours;
 gas-oil ratio 361:1; casing pressure 550 psi; gravity 38.2°
 API @ 60°F. COMPLETE.

Approved: *July 5 1951*
John R. Brown
 State Oil Inspector

Company Shell Oil Company
 Address Box 744, Great Bend, Kansas
 By *A. J. M. Long*
 Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate.