

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS



(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating..... X
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report..... X

19

Following is a ~~(notice of intention to drill)~~ (On land) ~~(report of work done)~~ described as follows:

Colorado	Logan	Mt. Hope
State	County	Field
2	C. F. GREEN "A"	NE SW NW Sec. 30-9N-53W
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 1015' ft. (N) of S line and 990' ft. (E) of W Line

The elevation above sea level is 4202 (df) ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Spud 11-14-50
8 5/8" 32# csg cem 352 w/ 200 sax. 4880-86 & 4889-91 w/ 52 kone shot.
Top Muddy 4857 Perforated Muddy 4873-78 w/ 24
15/32" bullets; 1-28-51.
Total Depth 5300 sand & shale; 12-5-50. Testing: Flow 35 1/2 bbls oil &
4 1/2" OD 9 1/2# csg cem 5285 w/ 200 sax. 821.3 MCF gas 24 hours 2-7-51.
Perforated 5248-62 w/ 56 shaped charges. On 2-15-51 testing through 10/64" choke. Flowing; no gauge.
Top Lakota 5208. Pump 7 bbls heavy
black oil & 1 bbl fresh water/24 hours
12-20-50 to 12-26-50.
Rigged up cable tools 1-10-51.
PBTD 5230. Perforated Dakota 4961-74
w/ 52 jet charges. 1,222 MCF gas/day.
PBTD 4915. Perforated Muddy 4871-73 w/
8 jet charges; 1-15-51.
PBTD 4910. Perforated Muddy 4873-78,

Note: When testing is completed "Log of Oil & Gas Well" report will be forwarded to your office.

Approved: *[Signature]*
State Oil Inspector

Company Shell Oil Company
Address Box 744, Great Bend, Kansas
By *[Signature]*
District Superintendent
Title

Submit reports of proposed work, for approval, on this form in Duplicate.