

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS



(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report. X.....

Following is a (~~notice of intention to do work~~) October 17, 1951
(report of work done) (On land) ~~(patented)~~ described as follows:

Colorado	Logan	Mt. Hope			
State	County	Field			
<u>9</u>	<u>C. F. Green "A"</u>	<u>SW/4 Section 30</u>	<u>9N</u>	<u>53</u>	
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)	(Twp.)	(Range)	(Meridian)

The well is located 1650 ft. (N) of S Line and 1650 ft. (E) of W Line
~~(S)~~ ~~(W)~~

The elevation above sea level is 4109 ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
ing points, and all other important proposed work.)

- 9-14-51 Spudded, ran and cemented 8 5/8" surface casing at 192' with 150 sacks.
- 9-22-51 Ran Schlumberger Log to TD 5026. Schlumberger Tops: Niobrara, 4013;
Timpas, 4335; Codell, 4393; Greenhorn, 4587; Muddy, 4853; Dakota, 4957.
- 9-22-51 Ran and cemented 5016', 4 1/2" OD, 9 1/2# casing at 5023' DF.
- 9-25-51 Perforated 4878-82 and 4854-78.
- 9-30-51 Flowed 528 bbls. oil, no water, 233 MCF/D in 24 hours, GOR 442.

COMPLETE

Approved: OCT 19 1951
J. J. Zwick
State Oil Inspector
Director

Company Shell Oil Company
Address 413 Denham Bldg., Denver, Colo.
By A. W. Wieders
Title Division Production Manager
For

Submit reports of proposed work, for approval, on this form in Duplicate.