




00202239

**OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO**



**SUNDRY NOTICES AND REPORTS ON WELLS**

**INSTRUCTIONS**

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☐

Notice of Intention to Change Plans

☐

Report of Recompletion

☐

Notice of Intention to Abandon Well

☒

Other

☐

(Check appropriate space)

LEASE NAME Tow Creek Federal WELL NO. 2FIELD Tow Creek WILDCAT                      COUNTY RouttLOCATION NE NE NW Section 19 Township 6N Range 86W Meridian 6th P.M.  
(Quarter Quarter)330 feet from N Section Line and 2310 feet from W Section Line  
N or S E or W

**(DETAILS OF WORK)**

This well is producing 3 B.O.P.D. and is uneconomical to produce.  
We propose the following:

1. Cement the open hole up into the casing with approx. 10 sx cement (2904' - 2940') and pull the 5 $\frac{1}{2}$ " casing.  
*TD*
2. Place a 10-sack plug at the bottom of the surface casing at 282' and pull the 10 3/4" surface casing.
3. A 10-sack plug will be placed at the surface and a dry hole marker erected.
4. Clean up and grade well and tank battery site.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Company Juniper Oil & Mining Co. Date May 10, 1960Address 415 C. A. Johnson Building Phone No. Ac-2-7797  
Denver 2, Colorado

Date

By Norman H. Warberg Title Pet. Engineer  
(Signature)

Director