




00264471

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☐

Notice of Intention to Change Plans

☐

Report of Recompleation

☒

Notice of Intention to Abandon Well

☐

Other

☐

(Check appropriate space)

LEASE NAME Carey WELL NO. C-1FIELD Mount Hope East WILDCAT COUNTY LoganLOCATION CNE SE (Quarter Quarter) Section 29 Township 9 N Range 53 W Meridian 6PM1980 feet from South Section Line and 660 feet from East Section Line
N or S E or W

(DETAILS OF WORK)

Pulled producing equipment and cleaned out to bottom. Drilled out Bridge Plug at 4910'KB and cleaned out to 5050'KB or TD. Ran Baker full bore Packer on 2" Tubing and set Packer at 4905'KB to test "J" sand. Well produced average of 870 MCF/D through various size Chokes. Pulled Tubing and Packer. Ran Production Packer on 2" Hydril Tubing and set Packer at 4903'KB. Tubing was bull plugged on bottom, perforated nipple at 4898'KB and Pump Seat at 4874'KB. Ran 1" Tubing and set in Packer for "J" sand gas production. Hooked up dual well head equipment and placed well on production. Well is currently producing 527.5 MCF gas from "J" sand and 95 barrels oil and 17 barrels water per day from "D" sand.

AJJ	
DVR	✓
FJK	
WRS	
HHA	
AH	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

AUG 14 1957

Date

Director

Company British-American Oil Date Aug. 13, 1957Address Box 180, Denver 1, Colo Phone No. AC 2 9401By Shamus M. Hogan Title Dist Supt.

(Signature)