



RECEIVED
DEC 4 - 1963

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

OIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input checked="" type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME CAREY WELL NO. C-1

FIELD Mount Hope East WILDCAT COUNTY Logan

LOCATION NE, SE Section 29 Township 9 N Range 53 W Meridian 6PM
 (Quarter Quarter)
1980 feet from south Section Line and 660 feet from east Section Line
 N or S E or W

(DETAILS OF WORK)

It is proposed to deepen this well from 5055 to 5300 and commingle the "O2" sand and "D" sand production by setting a 4" liner from 5300 to 5010 and perforating the "O2" zone with 4 jets per foot. The liner will overlap the present 5 1/2" casing string set at 5054, and leave the "D" and "J" sand perforations open to well bore. The "D" sand perforations are at 4842-4847 and "J" sand perforations are at 4947-4952. The top of "O" sand is estimated to be at 5207 & the "O2" at 5250. If necessary the "O2" zone will be sand-oil fractured through perforations with the Packer (on Tubing string) set above top of liner and below the "J" sand perforations. Will clean out to total depth and place on production. Your approval is requested. A report of recompletion will be submitted to your Office as soon as results are considered conclusive.

order 40-5

DVR	
WRS	
HMM	
JAM	
FJP	<input checked="" type="checkbox"/>
JD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:
 DEC 5 1963

 Date

 Director

Company British-American Oil Co Date 12-3-63
 Address Box 180, Denver, Colo Phone No. 222 9401
 By [Signature] Title Dist. Supt.
 (Signature)