




00264469

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☐

Notice of Intention to Change Plans

☐

Report of Recompletion

☒

Notice of Intention to Abandon Well

☐

Other

☐

(Check appropriate space)

LEASE NAME CAREY WELL NO. C-1FIELD Mount Hope East WILDCAT COUNTY LoganLOCATION NE, SE, Section 29 Township 9 N Range 53 W Meridian 6PM
(Quarter Quarter)1980 feet from South Section Line and 660 feet from East Section Line
N or S E or W

(DETAILS OF WORK)

Moved in Rotary Tools on 12-19-63. Drilled out the existing Bridge Plug at 4898 and a 4-3/4" hole to 5290'KB. Ran Sonic-Gamma Ray and ES Logs. Top of "O" sand per Schlumberger at 5203 and "O-2" sand at 5245'KB. Tested "O-2" interval 5244-5290. Initial shut in 30 minutes, Tool open 94 minutes, final shut in 30 minutes. Recovered 130' fluid consisting of 40' slightly oil cut mud and 90' water. IHP-2561, ISIP-2182, IFP-17, FFP-58, FSIP-1119 and FHP-2396. Had no gas to surface. Test is considered conclusive. Plugged hole with cement from 5290'KB to 5005'KB in preparation of returning well to "D" sand production only.

Enclosures: 1 copy each of Logs run and 1 copy of sample description, interval 5055-5290.

DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

MAR 6 1964

Date

Director

Company British-American Oil Co Date 3-4-64Address Box 180, Denver, Colo Phone No. 222 9401By Thomas M. Rogers Title Dist. Supt.
(Signature)