


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD



00238805

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Shell Oil Company Field Mt. Hope Wildcat
Lease Name C. F. Green "A" Tract "C" Well No. 18 County Logan
Location NW NE SE Section 30 Township 9N Range 53W Meridian 6 P.M.
(Quarter Quarter)
2290 feet from S Section line and 995 feet from E Section Line
N or S E or W

TOTAL DEPTH 5015 PBTD 4976 DATE OF PLUGGING 2/1/60

DETAILS OF WORK

Contractor: Donnelly Casing Pulling Unit

Dumped sand 4976 to 4827 feet. Capped with five sacks cement to 4789 feet. Shot and pulled 117 joints (3834') 4-1/2", 9.5# casing. Set 10 foot rock bridge at 461 feet. Filled with mud to 16 feet. Capped with five sacks cement to surface. P & A COMPLETE 2/1/60

p+a oil well

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date

FEB 24 1960

Director

Company Shell Oil Company
1845 Sherman Street
Address Denver 3, ColoradoDate 2-23-60Phone No. AComa 2-8454
Division Prod.
Title Superintendent

By

(Signature)
L. W. Elderkin

T

R ✓