

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS



(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report...X.....

Following is a (~~notice of intention to do work~~) (On land) February 19, 1952
(report of work done) (patented) described as follows:

Colorado Logan Mt. Hope
State County Field
10 C. F. Green "A" SW/4 Section 30 9N 53W
(Well No.) (Lease) (Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian)
The well is located 330 ft. (N) of N Line and 990 ft. (E) of
W Line (S) (W)

The elevation above sea level is 4176 DF ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
ing points, and all other important proposed work.)

12-15-51 Spudded and cemented 8 5/8" surface casing at 204' with 150 sacks.
12-26-51 Drilled to 5018 T.D. Ran Schlumberger survey. Cemented 5 1/2" at
5006 with 200 sacks. Waiting on cable tools.
1-14-52 Bailed hole. Perforated 4852-73 with 84 - 21 gram jets.
1-15-52 Ran tubing.
1-17-52 Flowed 200 bbls. oil, no water, 24 hours.
1-22-52 Flowed 75 bbls. oil, no water thru 16/64" choke in 24 hours.

COMPLETE

Schlumberger Tops: Niobrara 4020, Timpas 4333, Greenhorn 4584,
'Muddy' 4851, Dakota 4955.

Approved: FEB 21 1952
State Oil Inspector
DIRECTOR

Company Shell Oil Company
Address Denham Bldg., Denver 2, Colorado
By
Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate.