



COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

(Indicate nature of data by checking below)

- Notice of intention to drill _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report _____
- Completion Report XX

Following is a (notice of intention to do work) April 8, 19 52
(report of work done) (On land) (patented) described as follows:

Colorado	Logan	West Padroni
State	County	Field
<u>2</u>	<u>Francis Parke</u>	<u>NE/4 of Sec. 6</u>
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)
		<u>9-N</u>
		(Twp.)
		<u>52-W</u>
		(Range)
		<u>6th P.M.</u>
		(Meridian)

The well is located 990 ft. (N) of North line and 990 ft. (E) of West
line of NE/4 (S) (M)

The elevation above sea level is 4046 ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

The above well was drilled to a depth of 4845 feet, coring and drill stem testing as shown in detail on well log attached. We ran & cemented 7"OD casing - J-55 SS 8RT new - (1237' of 26# on bottom and 3607' of 20# on top) @ 4844' w/250 sx cement, after running Schlumberger electric log. We ran temperature survey and found the top of the cement to be approx. 4138 feet. We ran Lane-Wells Gamma Ray Survey w/plugged back total depth 4808 feet (we did not drill out the cement in the 7"OD casing).

3-17-52 Jet perforated MUDDY 4785-4790 w/10 - 7-oz. open hole shots.

3-22-52 COMPLETED - Swabbed 138 bbls. 38.5 API corrected gravity oil and no water thru tubing 24 hours from MUDDY perforations 4785-4790. Prepare install pumping equipment.

THREE COPIES WELL LOG ATTACHED. COPY SCHLUMBERGER ELECTRIC LOG ATTACHED.

Approved: APR 9 1952
[Signature]
Director

Company SINCLAIR OIL & GAS COMPANY
Address P O Box 1809, Casper, Wyoming
By [Signature]
Title Asst. Division Supt.

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.