



00238361

APR 4 1952

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

245-2

(Indicate nature of data by checking below)

Notice of intention to drill XX
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____

Following is a (notice of intention to do work) February 19, 19 52
 (~~report of work done~~) (On land) (patented) described as follows:

Colorado	Logan	Paroni	West Padroni
State	County	Field	
<u>2</u>	<u>Francis Parke</u>	<u>NE/4 of Sec. 6</u>	<u>9-N</u>
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)	(Twp.)
			<u>52-W</u>
			(Range)
			<u>6th P.M.</u>
			(Meridian)

The well is located 990 ft. (N) of North and 990 ft. (E) of West
lines of NE/4 (S) (W)

The elevation above sea level is 4046 ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

The above location has been selected to further develop our acreage surrounding Section
 6-9N-52W, Logan County, Colorado, testing the First Sand at approx. 4660 feet, the
 Muddy sand at approx. 4800 feet.

We will run and cement 10-3/4"OD 32.75# SS 8-V thread new casing at approx. 275 feet
 (cemented top to bottom). We will run and cement 7"OD J-55 new casing as the oil string.

We will drill this well with rotary tools.

Approved: APR 4 1952

Director

Company SINCLAIR OIL & GAS COMPANY

Address P O Box 1809, Casper, Wyoming

By
 Title Asst. Division Supt.

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.