




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

- Notice of intention to drill (attach plat) _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report _____

Locate Well Correctly

♀			
	16		

Notice to do work
Report of work done

Land: Fee and Patented
State

Lease No. 9032, Book 17
State of Colorado

Colorado
State

Logan
County

Walker
Field

#1 State Monahan & Zoller NW 16 9N 53W 6th
(Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 1650 Ft. ~~(N)~~ of Section Line and 330 Ft. (E) of ~~(W)~~ Section Line.

The elevation above sea level is 4105 Ft. (G.L.)
4117 K. B.

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Well was drilled to objective horizon to the 2nd bench of the "J" Sand and to a total depth of 4950 feet. There were no showings of either oil or gas in core cut from 4874' to 4914'. Schlumberger E. S. log was run and geologist recommended hole be abandoned. Hole was plugged by Halliburton Oil Well Cementing Company July 7, 1954. Hole was filled with heavy drilling mud from 4950' to 281'. Halliburton spotted 15 sack cement plug from 281' to 236' (bottom of surface casing 271'). Heavy drilling mud from 236' to surface. 5 sack cement top surface casing.

AJJ	
DVR	
FJK	
OPS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

Approved: MAR 22 1955

Date 3/21/55

A. J. Jervis
Director

Company JET DRILLING COMPANY, INC.

Address 409 California Bldg., Denver, Colo.

By Arthur M. Scott

Title for Operators

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

Handwritten notes: p. 19, T

