



Phone 522-1410

elly Casing Pulling Co. RECEIVED

P.O. Box 791
Sterling, Colorado 80751

SEP 15 1981 Bob Donnelly

SOLD TO Mr. Rex Monahan
Box 1231
Sterling, Colorado 80751

oil

COLORADO OIL & GAS CO. INC. (11)

INVOICE DATE 8-31-81

WELL State #1

INVOICE NO. 571

DVR	
FJP	
HHM	
JAM	✓
JJD	✓
RLS	
CGM	

Pulled rods & tubing		\$ 800.00
3636' 4½" OD Casing @	70¢ per foot	2545.20
Day Work, 22 hours @	\$50.00 per hour	1100.00
Water truck, 6 hours @	\$38.00 per hour	228.00
10% fuel surcharge		22.80
Shots, 2 @	\$30.00 per shot	60.00
Cement, 40 sacks @	\$6.50 each + tax	267.80
Welder, 4 hours @	\$21.00 per hour	84.00
Hauled rods & tubing to your yard:		
Int Truck, 7 hours @	\$42.00 per hour	294.00
10% fuel surcharge		29.40
Trailer, 7 hours @	\$12.00 per hour	84.00
Helper, 7 hours @	\$14.00 per hour	98.00
Hauled casing to your yard:		
Mack Truck #2, 7 hours @	\$42.00 per hour	294.00
10% fuel surcharge		29.40
Trailer, 7 hours @	\$12.00 per hour	84.00
Helper, 7 hours @	\$14.00 per hour	98.00
		<u>\$6118.60</u>

DATE	DAY WORK	REMARKS
8-18-81	0 hours	Moved on well. Raised mast. Hooked up lines. Worked rod loose.
8-19-81	0 hours	Pulled rods. Started pulling tubing.
8-20-81	10 hours	Finished pulling tubing. Dug cellar. Ran sand to 4870'. Set in jacks. Worked pipe to 36". Water truck, 3 hours.
8-21-81	8 hours	Finished loading hole. Dumped 5 sacks cement on sand. Worked pipe at 36". Shot at 3750' and 3620'. Worked loose. Pulled 30 joints. Water truck, 3 hours.
8-24-81	4 hours	Finished pulling casing, 102 total. Set 25 sacks cement in and out bottom of 8 5/8" at 114'. Mud-ded to 35'. Set 10 sacks cement to 3' below ground level. Tallied pipe. Lowered poles. Welded on cap.

WELL COMPLETE

THANK YOU