


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

LOG WILL FOLLOW

PLUGGING RECORD

OIL & GAS



INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Husker Oil Co. & Chancellor Oil Co. Field Wildcat X
Lease Name Elsie Good Well No. #1 County Logan
Location NE SW Section 13 Township 9N Range 54W Meridian 6th PM
(Quarter Quarter)
1980 feet from S Section line and 1980 feet from W Section Line
Nor S E or W

TOTAL DEPTH 5,145DATE OF PLUGGING 1-13-59

DETAILS OF WORK

The well was plugged January 13, 1959 by filling it with heavy mud from the total depth to 5 feet below the "D" Sand (4965-5065). Halliburton Oil Well Cementing Company spotted a 30 sack cement plug at 5065 - estimated fill-up 80 feet. A 10 sack cement plug was set in the bottom 30 feet of the surface pipe, casing was filled with heavy mud. A 7 sack cement plug was set in the top 20 feet of the surface pipe.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

*Well Drilled
in violation*

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date Jan 15 1959

Director

Company Exeter Drilling Company Date 1-14-59Address 919 Midland Savings Bldg. Phone No CH 4-8651By Wayne T. Bidder Title Vice President
(Signature)