


OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

## PLUGGING RECORD

OIL &amp; GAS

CONSERVATION COMMISSION

## INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Cabeen Exploration Corporation Field Hidden Valley Wildcat  
Lease Name Fitch Well No. 1 County Routt  
Location SE SE NW Section 6 Township 6N Range 86W Meridian 6th  
(Quarter Quarter)  
2310 feet from N Section line and 2310 feet from W Section Line  
N or S E or W

TOTAL DEPTH 3723DATE OF PLUGGING 12/3/60

## DETAILS OF WORK

- 13 3/8" surface casing cemented at 345'  
5 1/2" casing cemented at 3657'  
5" open hole to 3723'
1. Pushed plug to 3500'.
  2. Filled w/sand and rock to 3470'.
  3. Plugged from 3470 to 3430 w/5 sx cement.
  4. Shot 5 1/2" casing at 2592' and pulled.
  5. Filled hole w/mud.
  6. Set 25 sack plug 360 - 330.
  7. Set 10' sack plug 12' to surface.
  8. Erected marker.

AJJ	
DVR	
WRS	
HHM	
JAM	✓
FJP	✓
JJD	✓
FILE	

*Plugging checked on 6/19/61 P. H. A. Oil*

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JAN 23 1961

Director

Company Cabeen Exploration Corp. Date 1-20-61Address 945 Petroleum Club Bldg. Phone No. Am 6-1635

By

(Signature)

Title