

MERIDIAN OIL, INC
23-11 KLINE
YAMPA PROSPECT
NESW SEC 11-T7N-R91W
MOFFAT COUNTY, COLORADO

KB ELEV 6520'
GR ELEV 6505'

9-5/8", 36#, K-55 @ 1104'
Cemented to surface w/ 660 sx Class 'G'

TOC 1480'

Mesa Verde Coal
5526-5666'
Gross Perforated Interval

PBTD 5720'
CIBP 5730 w/ 10 sx cmt on top

5-1/2", 20#, N80 LTC @ 5750'
Cemented w/ 1270 sx Class 'G'

TD 5805'

Open Hole
Mesa Verde Coal
5750-5805'



00221914