

STATE OF COLORADO
OIL AND GAS CONSERVATION COMMISSION
DEPARTMENT OF NATURAL RESOURCES

APPLICATION
FOR PERMIT TO DRILL, DEEPEN, OR RE-ENTER AND OPERATE

1a. TYPE OF WORK
DRILL ☒ DEEPEN ☐ RE-ENTER ☐ SOLO OIL & GAS ☐ COMM. ☐

b. TYPE OF WELL
OIL WELL ☐ GAS WELL ☒ OTHER ☐

2. NAME OF OPERATOR
Chandler & Associates, Inc.

3. ADDRESS OF OPERATOR
1860 Lincoln St, Suite 1400 Denver, CO 80203

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)
At surface 1878' FNL; 1928' FEL SW NE
At proposed prod. zone same

5. LEASE DESIGNATION AND SERIAL NO.
82-7309-S

6. INDIAN, ALLOTTEE OR TRIBE NAME
COMM.

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
NE Craig St.

9. WELL NO.
7-16

10. FIELD AND POOL, OR WILDCAT
Wildcat

11. SEC., T., R., M. OR BLK. AND SURVEY OR AREA
Sec. 16-7N-90W

12. COUNTY
Moffat

13. STATE
Colorado

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE
Approximately 5 miles North of Craig, Colorado

15. DISTANCE FROM PROPOSED LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT.
(Also to nearest drig. line, if any) 1878'

16. NO. OF ACRES IN LEASE*
640

17. NO. OF ACRES AND/OR DRILLING UNIT ASSIGNED TO THIS WELL
320

18. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.
--

19. PROPOSED DEPTH
2900'

20. ROTARY OR CABLE TOOLS
Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
6299' (ground)

22. APPROX. DATE WORK WILL START

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8-5/8"	24#	300'	200SX
7-7/8"	5 1/2"	15.5#	2900'	200 SX

24. IS SURFACE OWNER A PARTY TO LEASING AGREEMENT? YES ☒ NO ☐
If NO, surface bond must be on file.

DESCRIBE LEASE

1. Drill to TD of 2900' (Lewis).
2. Run 5 1/2" casing if commercial production is indicated.
3. If dry hole, plug and abandon as instructed by the State of Colorado.
4. Mud program will be chemical gel to TD with Mud-up at approximately 2300'.
5. Well control equipment will be furnished by the drilling contractor and will include a double hydraulic system of 900 series. A fillup line will be installed and equipment will be mechanically checked daily while drilling.

Lease Description: All of Sec. 16-7N-90W, Moffat County, Colo.

SIGNED Richard Veghte TITLE Petroleum Engineer DATE December 15, 1986

(This space for Federal or State Office use)

PERMIT NO. 86-857 APPROVAL DATE DEC 17 1986 EXPIRATION DATE APR 16 1987

APPROVED BY William Smith TITLE DIRECTOR DATE DEC 17 1986
O & G Cons. Comm.

CONDITIONS OF APPROVAL, IF ANY:



See

00221837

A.P.I. NUMBER

05 081 6662