




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

144-7

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well ☒ _____
 Report of work done on well since previous report Drilled and Cored to TD 5051'

Following is a (notice of intention to do work) November 25 19 52
 (report of work done) (On land) (patented) described as follows:

Colorado Logan Walker Area
State County Field
10-17-52
1 Strouse SE/4, Sec. 28 9 North 53 West 6th P.M.
 (Well No.) (Lease) (Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 1980 ft. (N) of South line and 1980 ft. (E) of
 (S) (W)

West line, Sec. 28

The elevation above sea level is 4175 Gr.
4187 KB ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

Fill hole from TD 5051' to 250' with heavy mud (10.3# Gal.)
 Cement plug of 35 sacks cement from 200' to 135' and plug
 of 15 sacks cement from 40' to top 10-3/4" Casing.

Schlumberger Tops: Niobrara - 4023
 Ft. Hays - 4322
 Codell - 4365
 Greenhorn - 4578
 "D" Sand - 4818
 "J" Sand - 4916
 Skull Creek - 5035

Total Depth: 5051' - Driller and Schlumberger

Approved: DEC 4 1952
J. J. Zarichok
 Director

Company VAUGHY AND VAUGHY
 Address 312 C. A. Johnson Bldg.
 By W. T. Blackburn
 Title Partner

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.