


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompletion ☒Notice of Intention to Abandon Well ☐Other ☐

(Check appropriate space)

LEASE NAME C. W. Piper WELL NO. #1FIELD East Mt. Hope WILDCAT COUNTY LoganLOCATION C SE NE Section 29 Township 9N Range 53W Meridian

(Quarter Quarter)

660 feet from N Section Line and 660 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

Well Status Prior to Workover:

Total Depth 5045; Plug Back Depth 4998; Elevation 4204 KB

"D" Sand 4850 (-646) "J" Sand 4947 (-743)

Completion Interval: 4850-56

Present Prod: 0.7 BOPD, 10 BWPD, GOR 23,000:1

Total cumulative production: 3575 Bbl oil; 5,964 Bbl water, 161,066 MCFG

"D" Sand Reservoir Abandoned 22 August 1956

Recompletion Work Performed:

Plug Back Depth: 4998

Squeezed "D" Sand perforation 4850-56 with 60 sacks Portland cement @ max press 3500 psi

Drilled out cement and tested squeezed off perforations. No fluid entry. Perforated

"J" Sand 4968-74 with 4 Koneshots per foot. Ran 2" tubing & packer. Swabbed well in

28 August 1956.

Tested 2,880 MCFD 20/64" choke TP 990# Shut In TP 1150#

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

SEP 17 1956

Date

Director

Company J. Ray McDermott & Co., Inc. Date 14 Sept., 1956Address 222 Midland Svgs. Bldg. Phone No. Ac 2-5694

Denver, Colorado

By John F. Winkley
(Signature)Title Prod. Supt.