

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED

APR -5 1968

COLO. OIL & GAS CONS. COMM.

PLUGGING RECORD



99999999

#075-06551

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator A. T. Skaer Field Cedar Creek Wildcat
Lease Name Britton Well No. C-2 County Logan
Location C-SW SE SW Section 7 Township 9N Range 53W Meridian 6th Pm
(Quarter Quarter)
330 feet from S Section line and 1650 feet from W Section Line
N or S E or W

No Prior Approval

TOTAL DEPTH 5170'DATE OF PLUGGING 3/21/68

DETAILS OF WORK

Purchased well from Gulf Oil Corporation and attempted to clean up well and make commercial producer but did not respond.
M.I.R.U. Run sand to 4914', dumped 5 sax cement to 4872'. Worked casing to 34" tension. Shot at 4110', 4020', and 3960', worked loose and pulled 124 joints. Mud to 215', run 15 sax cement to 180', mud to 18', run 5 sax cement to base cellar and welded on cap.

DVR	
FJP	✓
HUN	✓
JAN	✓
JD	✓

Ex
oil
Prod.

00817964

Note: Art Skaer called on 4/4/68, apologized for not getting prior approval to P&A. Jim

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date APR 10 1968

Director

Company A. T. SkaerDate 4/4/68

920 Patterson Building

Address Denver, Colorado 80202 Phone No. 534-0121

By

(Signature)

Title